

INVITATION TO BIDS

Sealed bids for the City of Farmington, Missouri (hereinafter "Owner") Highway H Sidewalk Improvements, Tap-2500(008) (hereinafter "Project") will be received by the City of Farmington, 12 South Franklin Street, Farmington, Missouri 63640, until 2:00 p.m. local time, on Tuesday, November 5, 2024, at which time the bids will be publicly opened and read aloud.

The Scope of Work includes sidewalk improvements to Highway H within the City of Farmington and provides for concrete sidewalks and ADA ramps, concrete approach, concrete curb and gutter, storm sewer improvements, pavement striping, traffic control and other incidental items and work described in the Project Manual, or reasonably inferable therefrom. Farmington, Missouri anticipates issuing notice to proceed in the early spring of 2025, weather permitting.

To ensure that you receive all addenda, request the bid documents by email from Becky Toney at btoney@cochraneng.com. Bid packages will be distributed electronically at no cost to the bidder. When requesting the documents, you will be required to provide your company name, a contact person and phone number, a complete company address and an e-mail address to be added to the Plan Holders List and for receiving official bidding communications and addenda. If you are not on the Plan Holders List, you will not receive any addenda issued. Hard copies will not be available for purchase. Bidders may make printed copies of the bid documents (plans, project manual, and a bid packet) at their own expense. Project and bidding questions shall be conducted exclusively via e-mail. Any questions regarding this project must be submitted to: mspalding@cochraneng.com, by 4:00 pm local time on October 29, 2024. No written questions after this date or any verbal questions will be recognized.

A bid security in the amount of five percent (5%) of the bid amount must accompany each bid, in accordance with the Instructions to Bidders.

For a contractor to be awarded this project the contractor must have a fully responsive contractor questionnaire on file with the Missouri Highway and Transportation Commission at least 7 days prior to the bid opening date. All bidders must be on MoDOT's Qualified Contractor List per Section 102.2 of the 2023 Missouri Standard Specifications for Highway Construction. No Second Tier Subcontracting will be allowed.

The wage rates applicable to this project have been predetermined as required by law and are set forth in this specification. When Federal wage rates are applicable and included, this contract is subject to the "Work Hours Act of 1962", (P.L. 87-581: 76 Stat. 357) and implementing regulations. When state and federal wage rates are both required the higher of the two for each job classification shall be used.

Effective January 1, 2009 and pursuant to RSMo 285.530 (1), No business entity or employer shall knowingly employ, hire for employment, or continue to employ an unauthorized alien to perform work within the state of Missouri. The successful bidder must submit a sworn affidavit and documentation affirming the business entity's enrollment and participation in the federal work authorization program and that all of its employees working for the contracted services are not illegal immigrants.

Upon signing the contract, the successful contractor and any subcontractor performing the work shall provide a ten-hour Occupational Safety and Health Administration (OSHA) construction safety program for their on-site employees within sixty (60) days of beginning work on the construction project.

The City of Farmington, Missouri hereby notifies all bidders that it will affirmatively ensure that in any contract entered into pursuant to this advertisement, businesses owned and controlled by socially and economically disadvantaged individuals will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, religion, creed, sex, age, ancestry, or national origin in consideration for an award.

The DBE Contract Goal for this project is 5%, and DBE firms must be certified by MoDOT to attain credit towards this contract goal. There is no On-the-Job Trainee goal.

THE OWNER INTENDS TO AWARD THE CONTRACT TO THE LOWEST, RESPONSIVE, RESPONSIBLE BIDDER. THE OWNER RESERVES THE RIGHT TO REJECT ANY AND ALL BIDS, AND TO WAIVE ANY IRREGULARITIES IN THE BEST INTEREST OF THE OWNER WITH MODOT'S CONSENT.

Drawing name: U:\SC23-1479 Hwy H TAP Sidewalks, Farmington, MO\AUTOCAD DRAWINGS\QUANTITY SHEET.dwg Tab: Q-1 Plotted on: Aug 09, 2024 -- 9:59am Plotted by: kwolff

QUANTITY SHEET

| Bid No. | Spec. No. | Description | From STA | To STA | Unit | Quantity |
|---------|-----------|--|----------|--------|------|----------|
| | | ROADWAY ITEMS | | | | |
| 1 | 1042003 | New Mailbox and Post | 39+45 | 66+46 | EA | 5 |
| 2 | 2013000 | Clearing and Grubbing | 34+55 | 70+61 | AC | 0.1 |
| 3 | 2013001 | Stump Removal | 36+35 | 66+40 | EA | 11 |
| 4 | 2022010 | Removal of Improvements | 34+55 | 70+61 | LS | 1 |
| 5 | 2038000 | Earthwork | 34+55 | 70+61 | STA | 36 |
| 6 | 2063100 | Class 3 Excavation in Rock | 35+22 | 69+32 | CY | 100 |
| 7 | 5021100 | Concrete Pavement (7") (12" Wide for Mounting Existing Railing) Non-Reinforced | 34+65 | 34+95 | SF | 42 |
| 8 | 5021100 | Full Depth Concrete Pavement (8") Non-Reinforced | 34+67 | 34+97 | SY | 230 |
| 9 | 6085000 | Concrete Approach, 7" (Remove and Replace) | 38+05 | 70+61 | SF | 10,090 |
| 10 | 6131000 | Concrete Curb and Gutter, 6" (3' Wide) | 34+59 | 41+94 | LF | 675 |
| 11 | 6143020 | Storm Sewer Structure (MODOT Drop Inlet, Type 2) | 35+47 | 40+47 | EA | 4 |
| 12 | 6143020 | Storm Sewer Structure (48" Manhole) | 41+91 | 41+91 | EA | 1 |
| 13 | 6143020 | Storm Sewer Structure (60" Manhole) | 35+22 | 35+25 | EA | 2 |
| 14 | 6143020 | Storm Sewer (36" HDPE) | 35+22 | 37+78 | LF | 275 |
| 15 | 6143020 | Storm Sewer (15" HDPE) | 37+78 | 41+91 | LF | 414 |
| 16 | 6143020 | Storm Sewer (15" RCP) | 44+02 | 69+32 | LF | 363 |
| 17 | 6161025 | Channelizers (Trimline) | 34+55 | 70+61 | EA | 50 |
| 18 | 6181000 | Mobilization | 34+55 | 70+61 | LS | 1 |
| 19 | 7320612A | Precast Concrete Flared End Section, 15" | 43+96 | 69+38 | EA | 24 |
| 20 | 7339900 | Storm Sewer (4'x2' Box Culvert Extention) | 37+76 | 37+80 | LF | 5 |
| 21 | 8061007A | Inlet Check | 35+47 | 40+47 | EA | 4 |
| 22 | 8061019 | Silt Fence | 35+32 | 69+87 | LF | 3,180 |
| 23 | JSP | 6" Watermain Relocation | 35+40 | 35+50 | EA | 1 |
| 24 | JSP | Subgrade Repair | 34+55 | 70+61 | CY | 10 |
| | | SIGNING/STRIPING/SIGNALS ITEMS | | | | |
| 25 | 6161006 | "Road Work Ahead" Sign (W20-1) | 34+55 | 70+61 | EA | 2 |
| 26 | 6161006 | "Shoulder Work Ahead" Sign (W21-5) | 34+55 | 70+61 | EA | 2 |
| 27 | 6161006 | "End Road Work" Sign (G20-2) | 34+55 | 70+61 | EA | 2 |
| 28 | 6161006 | "One Lane Road Ahead" Sign (W20-4) | 34+55 | 70+61 | EA | 2 |
| 29 | 6161006 | "Flagger" Sign (W20-7a) | 34+55 | 70+61 | EA | 2 |
| 30 | 6200035 | Pavement Marking - Crosswalk Striping, White (Preformed Thermoplastic) | 34+55 | 35+30 | SF | 233 |
| 31 | 6206124A | Pavement Marking 24" - Stop Bar, White (Preformed Thermoplastic) | 34+90 | 35+03 | LF | 14 |
| 32 | 9031200 | Sign Relocation on New Post (per location, regardless of the number of signs) | 35+75 | 35+75 | EA | 2 |
| | | BICYCLE/PEDESTRIAN FACILITY ITEMS | | | | |
| 33 | 6071000 | Remove and Relocate Pedestrian Rail | 34+55 | 34+95 | LF | 57 |
| 34 | 6086000 | Concrete Sidewalk, 4" | 34+55 | 69+90 | SF | 16,512 |
| 35 | 6081012 | Detectable Warning Device | 34+65 | 69+90 | SF | 45 |
| | | LANDSCAPING/STREETSCAPING ITEMS | | | | |
| 36 | 8031000 | Sodding | 34+55 | 70+61 | SY | 3,700 |

314-842-4033 (tel.)
314-842-5957 (fax)
www.cochraneng.com

COCHRAN

Civil Engineering
Land Surveying
Architecture
Site Development
Master Planning
General Consulting

737 RUDDER ROAD
FENTON, MISSOURI 65026

ENGINEERING CERTIFICATE OF AUTHORITY NUMBER - 200706937
LAND SURVEYING CERTIFICATE OF AUTHORITY NUMBER - 2007064529

STATE OF MISSOURI

KEVIN J. WOLFF, P.E.

6/10/2024

KEVIN J. WOLFF
NO. PE-200400889
STATE OF MISSOURI
REGISTERED PROFESSIONAL ENGINEER
FOR SC ENGINEERING LLC,
DBA COCHRAN

THIS SHEET HAS BEEN SIGNED,
SEALED AND DATED ELECTRONICALLY

THE PROFESSIONAL'S SEAL AFFIXED TO
THIS SHEET APPLIES ONLY TO ITEMS
ON THIS SHEET. ALL DRAWINGS OR
OTHER DOCUMENTS NOT EXHIBITING
THIS SEAL SHALL NOT BE CONSIDERED
PREPARED BY THIS PROFESSIONAL.

HIGHWAY H SIDEWALK IMPROVEMENTS
FEDERAL PROJECT NO. TAP-2500(008)
CITY OF FARMINGTON, MISSOURI

QUANTITY SHEET

| | | | |
|-----------|-----------|----------|-----------|
| DATE: | REVISION: | DWN. BY: | APPR. BY: |
| | | S.R.B. | K.J.W. |
| DATE: | | | |
| SCALE: | | | |
| | | | |
| PROJ. NO: | | | |
| | | | |
| DWG. NO: | | | |

Q-1