

INVITATION TO BIDS

Sealed bids for the Franklin County, Missouri (hereinafter "Owner") St. John's Creek Road Bridge Replacing Low Water Crossing Project, BRO-R036(002) (hereinafter "Project") will be received by the Franklin County Commission, 400 E. Locust Street, Union, Missouri, 63084, until 2:00 p.m. local time, on Thursday, April 23, 2026, at which time the bids will be publicly opened and read aloud.

The Scope of Work includes removal of the low water crossing on St. John's Creek Road crossing St. John's Creek, construction of a new bridge near the same location, and provides for excavations, pile driving, bridge construction, embankments, asphalt paving, pavement striping, guard rail, traffic control, fencing and other incidental items and work described in the Project Manual, or reasonably inferable therefrom. Franklin County anticipates issuing notice to proceed in the spring of 2026.

To ensure that you receive all addenda, request the bid documents by email from Becky Toney at btoney@cochraneng.com. Bid packages will be distributed electronically at no cost to the bidder. When requesting the documents, you will be required to provide your company name, a contact person and phone number, a complete company address and an e-mail address to be added to the Plan Holders List and for receiving official bidding communications and addenda. If you are not on the Plan Holders List, you will not receive any addenda issued. Hard copies will not be available for purchase. Bidders may make printed copies of the bid documents (plans, project manual, and a bid packet) at their own expense. Project and bidding questions shall be conducted exclusively via e-mail. Any questions regarding this project must be submitted to: mspalding@cochraneng.com, by 4:00 pm local time on April 16, 2026. No written questions after this date or any verbal questions will be recognized.

A bid security in the amount of five percent (5%) of the bid amount must accompany each bid, in accordance with the Instructions to Bidders.

For a contractor to be awarded this project the contractor must have a fully responsive contractor questionnaire on file with the Missouri Highway and Transportation Commission at least 7 days prior to the bid opening date. All bidders must be on MoDOT's Qualified Contractor List per Section 102.2 of the 2025 Missouri Standard Specifications for Highway Construction.

The wage rates applicable to this project have been predetermined as required by law and are set forth in this specification. When Federal wage rates are applicable and included, this contract is subject to the "Work Hours Act of 1962", (P.L. 87-581: 76 Stat. 357) and implementing regulations. When state and federal wage rates are both required the higher of the two for each job classification shall be used.

Effective January 1, 2009 and pursuant to RSMo 285.530 (1), No business entity or employer shall knowingly employ, hire for employment, or continue to employ an unauthorized alien to perform work within the state of Missouri. The successful bidder must submit a sworn affidavit and documentation affirming the business entity's enrollment and participation in the federal work authorization program and that all of its employees working for the contracted services are not illegal immigrants.

Upon signing the contract, the successful contractor and any subcontractor performing the work shall provide a ten-hour Occupational Safety and Health Administration (OSHA) construction safety program for their on-site employees within sixty (60) days of beginning work on the construction project.

Franklin County, Missouri hereby notifies all bidders that it will affirmatively ensure that in any contract entered into pursuant to this advertisement, businesses owned and controlled by socially and economically disadvantaged individuals will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, religion, creed, sex, age, ancestry, or national origin in consideration for an award.

The DBE Contract Goal for this project is 0%, and DBE firms must be certified by MoDOT to attain credit towards this contract goal. There is no goal for On the Job Trainee.

THE OWNER INTENDS TO AWARD THE CONTRACT TO THE LOWEST, RESPONSIVE, RESPONSIBLE BIDDER. THE OWNER RESERVES THE RIGHT TO REJECT ANY AND ALL BIDS, AND TO WAIVE ANY IRREGULARITIES IN THE BEST INTEREST OF THE OWNER WITH MODOT'S CONSENT.

Drawing name: U:\sc23-1469 st. johns rd bridge - franklin co lwc\AUTOCAD DRAWINGS\QUANTITIES.dwg Tab: Q-1 Plotted on: Jan 28, 2026 - 12:45pm Plotted by: BDunagan

QUANTITIES

Bid	Spec.	Description	From STA	To STA	Unit	Quantity
ROADWAY ITEMS						
1	2013000	Clearing and Grubbing	13+00	19+47	AC	0.5
2	2022010	Removal of Improvements (Low Water Crossing)	15+75	16+75	LS	1
3	2035000	Unclassified Excavation	13+00	19+47	CY	20
4	2035500	Embankment in Place	13+00	19+47	CY	4100
5	3105002	Gravel (A) or Crushed Stone (B)	13+00	19+47	TON	150
6	3109910	3" Minus Base Course (9")	13+00	19+47	TON	470
7	6061010	Type A Guardrail	17+51	17+77	LF	50
8	6062401	Bridge Anchor Section	15+06	17+45	EA	4
9	6063015	Type A Crashworthy End Terminal (50')	14+49	18+28	EA	4
10	6062304	Assymetrical Transition Section, 7.5 Ft. Posts	14+99	18+28	EA	4
11	6072005	5-Strand Barbed Wire Fence	17+00	17+84	LF	70
12	6072009	Temporary Fencing	17+00	17+90	LF	90
13	6181000	Mobilization	13+00	19+47	LS	1
14	6274000	Contractor Furnished Surveying and Staking	13+00	19+47	LS	1
15	8061019	Silt Fence	13+00	19+47	LF	852
16	8061021	Type I Ditch Check	18+00	18+50	EA	2
SIGNING/STRIPING/SIGNAL ITEMS						
17	6161005	Construction Signs	13+00	19+47	SF	125
18	9035000	Stop Sign on New Post (30" x 30")	19+19	19+20	EA	1
19	6161030	Type III Moveable Barricade with Light	13+00	19+47	EA	8
20	6161096	Changeable Message Sign	13+00	19+47	EA	2
LANDSCAPING/STREETSCAPING ITEMS						
21	8051000A	Seeding - Cool Season Mixtures	13+00	19+47	AC	0.7
BRIDGE ITEMS						
22	2061001	Class 1 Excavation	15+38	17+14	CY	200
23	5031010	Bridge Approach Slab	15+19	17+33	SY	125
24	6111000	3" Minus Rock Blanket Fill (Furnish & Place)	15+39	17+12	TON	35
25	6113020	Furnishing Type 2 Rock Blanket	15+29	17+23	TON	1700
26	6113040	Placing Type 2 Rock Blanket	15+29	17+23	TON	1700
27	7021210	Galvanized Structural Steel Piles (10 IN)	15+39	17+12	LF	325
28	7021212	Galvanized Structural Steel Piles (12 IN)	16+25	16+27	LF	256
29	7027000	Pile Point Reinforcement	15+39	17+12	EA	18
30	7032003	Class B Concrete (Substructure)	15+39	17+12	CY	85.0
31	7033002	Work Pad - Intermediate Bent	16+24	16+28	EA	1
32	7034212	Slab on Concrete NU-Girder	15+39	17+12	SY	890
33	7034219A	Type D Barrier	15+19	17+32	LF	426
34	7056021	NU 35, Prestressed Concrete NU-Girder	15+40	17+12	LF	684
35	7101000	Reinforcing Steel (Epoxy Coated) (Grade 60)	15+39	17+13	LB	14740
36	7123610S	Slab Drain (Steel)	15+39	17+12	EA	28
37	7151001	Vertical Drain at End Bents	17+12	17+13	EA	1
38	7161000	Plain Neoprene Bearing Pads	15+40	17+12	EA	16

314-842-4033 (tel.)
314-842-5957 (fax)
www.cochraneng.com

COCHRAN
Civil Engineering
Land Surveying
Architecture
Site Development
Master Planning
General Consulting

1735 WESTPARK CENTER DR.
FENTON, MISSOURI 65026

ENGINEERING CERTIFICATE OF AUTHORITY NUMBER - 2007006937
LAND SURVEYING CERTIFICATE OF AUTHORITY NUMBER - 2007004529

STATE OF MISSOURI
BRADFORD DUNAGAN
NO. E-22970
STATE OF MISSOURI
REGISTERED PROFESSIONAL ENGINEER
FOR SC ENGINEERING LLC,
DBA COCHRAN

1/27/2026
THIS SHEET HAS BEEN SIGNED,
SEALED AND DATED ELECTRONICALLY

THE PROFESSIONAL'S SEAL AFFIXED TO
THIS SHEET APPLIES ONLY TO ITEMS
ON THIS SHEET. ALL DRAWINGS OR
OTHER DOCUMENTS NOT EXHIBITING
THIS SEAL SHALL NOT BE CONSIDERED
PREPARED BY THE PROFESSIONAL.

ST. JOHN'S CREEK RD. BRIDGE NO. 0590007
REPLACING LOW WATER CROSSING
FEDERAL PROJECT NO. BRO-R036(002)
FRANKLIN COUNTY, MISSOURI

QUANTITIES

DATE: REVISION:

DWN BY: A.J.M. APPD BY: B.B.D.

DATE: JAN. 2026

SCALE: NOT TO SCALE

PROJ. NO: SC23-1469

DWG. NO: Q-1