

**INVITATION TO BIDS**

Sealed bids for the City of St. Clair, Missouri (hereinafter "Owner") Walton Street and Jean Street Sidewalks to Schools, TAP-5489(615), (hereinafter "Project") will be received by St. Clair City Hall, 1 Paul Parks Drive, St. Clair, Missouri 63077, until 10:00 a.m. local time, on Thursday, August 20, 2026, at which time the bids will be publicly opened and read aloud.

The Scope of Work includes sidewalk improvements to Walton and Jean Streets within the City of St. Clair and provides for pavement widening, concrete sidewalk, concrete curb and gutter concrete approach, asphalt driveway, crosswalk striping, traffic control and other incidental items and work described in the Project Manual, or reasonably inferable therefrom. St. Clair anticipates issuing notice to proceed in the fall of 2026.

To ensure that you receive all addenda, request the bid documents by email from Becky Toney at [btoney@cochraneng.com](mailto:btoney@cochraneng.com). Bid packages will be distributed electronically at no cost to the bidder. When requesting the documents, you will be required to provide your company name, a contact person and phone number, a complete company address and an e-mail address to be added to the Plan Holders List and for receiving official bidding communications and addenda. If you are not on the Plan Holders List, you will not receive any addenda issued. Hard copies will not be available for purchase. Bidders may make printed copies of the bid documents (plans, project manual, and a bid packet) at their own expense. Project and bidding questions shall be conducted exclusively via e-mail. Any questions regarding this project must be submitted to: [mspalding@cochraneng.com](mailto:mspalding@cochraneng.com), by 4:00 pm local time on August 13, 2026. No written questions after this date or any verbal questions will be recognized.

A bid security in the amount of five percent (5%) of the bid amount must accompany each bid, in accordance with the Instructions to Bidders.

For a contractor to be awarded this project the contractor must have a fully responsive contractor questionnaire on file with the Missouri Highway and Transportation Commission at least 7 days prior to the bid opening date. All bidders must be on MoDOT's Qualified Contractor List per Section 102.2 of the current Missouri Standard Specifications for Highway Construction.

The wage rates applicable to this project have been predetermined as required by law and are set forth in this specification. When Federal wage rates are applicable and included, this contract is subject to the "Work Hours Act of 1962", (P.L. 87-581: 76 Stat. 357) and implementing regulations. When state and federal wage rates are both required the higher of the two for each job classification shall be used.

Effective January 1, 2009 and pursuant to RSMo 285.530 (1), No business entity or employer shall knowingly employ, hire for employment, or continue to employ an unauthorized alien to perform work within the state of Missouri. The successful bidder must submit a sworn affidavit and documentation affirming the business entity's enrollment and participation in the federal work authorization program and that all of its employees working for the contracted services are not illegal immigrants.

Upon signing the contract, the successful contractor and any subcontractor performing the work shall provide a ten-hour Occupational Safety and Health Administration (OSHA) construction safety program for their on-site employees within sixty (60) days of beginning work on the construction project.

The City of St Clair, Missouri hereby notifies all bidders that it will affirmatively ensure that in any contract entered into pursuant to this advertisement, businesses owned and controlled by socially and economically disadvantaged individuals will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, religion, creed, sex, age, ancestry, or national origin in consideration for an award.

The DBE Contract Goal for this project is 0%, and DBE firms must be certified by MoDOT to attain credit towards this contract goal. There is no on the Job Trainee goal.

**THE OWNER INTENDS TO AWARD THE CONTRACT TO THE LOWEST, RESPONSIVE, RESPONSIBLE BIDDER. THE OWNER RESERVES THE RIGHT TO REJECT ANY AND ALL BIDS, AND TO WAIVE ANY IRREGULARITIES IN THE BEST INTEREST OF THE OWNER WITH MODOT'S CONSENT.**

Drawing name: U:\SC23-1512 Walton & Jean TAP Sidewalks, St. Clair, MO\AUTOCAD DRAWINGS\QUANTITY SHEET.dwg Tab: Q-1 Plotted on: May 18, 2026 - 3:03pm Plotted by: MSPolding

QUANTITY SHEET

| Bid No. | Spec. No. | Description                                                                                                            | N. Walton St. |          | S. Walton St. |           | Jean st.  |           | Unit | Quantity |
|---------|-----------|------------------------------------------------------------------------------------------------------------------------|---------------|----------|---------------|-----------|-----------|-----------|------|----------|
|         |           |                                                                                                                        | From STA      | To STA   | From STA      | To STA    | From STA  | To STA    |      |          |
|         |           | <b>ROADWAY ITEMS</b>                                                                                                   |               |          |               |           |           |           |      |          |
| 1       | 2013000   | Clearing and Grubbing                                                                                                  | -             | -        | 102+38.31     | 102+82.20 | -         | -         | AC   | 0.1      |
| 2       | 2013001   | Tree Removal                                                                                                           | -             | -        | -             | -         | 203+20.40 | 203+34.16 | EA   | 2        |
| 3       | 2022010   | Removal of Improvements                                                                                                | 10+34.80      | 17+32.59 | 100+00.00     | 110+04.55 | 200+08.12 | 205+47.32 | LS   | 1        |
| 4       | 2038000   | Earthwork                                                                                                              | 10+34.80      | 17+32.59 | 100+00.00     | 110+04.55 | 200+08.12 | 205+47.32 | STA  | 22.4     |
| 5       | 4011000   | Asphalt Driveway, 5" (BP-2) (Remove and Replace)                                                                       | 11+71.08      | 12+73.91 | 105+62.29     | 105+80.09 | -         | -         | SF   | 662      |
| 6       | 4011209   | Asphalt Pavement Surface Course, (**Hot Joints Required** See Job Special Provisions Section 401) (BP-1)(2" )(PG64-22) | 10+34.80      | 17+32.59 | 100+00.00     | 110+04.55 | 200+08.12 | 205+47.32 | TON  | 76       |
| 7       | 6085000   | Concrete Approach, 6" (Remove and Replace)                                                                             | 11+71.27      | 16+84.28 | 100+92.98     | 109+74.35 | 200+70.10 | 204+76.69 | SF   | 10,099   |
| 8       | 6091012   | Concrete Vertical Curb, 6"                                                                                             | 17+05.36      | 17+19.82 | -             | -         | 205+45.76 | 205+46.24 | LF   | 48       |
| 9       | 6091053   | Concrete Curb and Gutter                                                                                               | 10+34.80      | 17+32.59 | 100+00.00     | 110+04.55 | 200+14.50 | 205+39.22 | LF   | 2,111    |
| 10      | 6131000   | Full Depth Pavement (Widening) (Includes sawcuts, removals, aggregate base and concrete)                               | 10+34.80      | 17+32.59 | 100+00.00     | 110+04.55 | 200+08.12 | 205+47.32 | SY   | 668      |
| 11      | 6131000   | Utility Cut Pavement Repair (Concrete and Sawcuts) (Storm Sewer Pipe & Structures)                                     | -             | -        | 102+59.05     | 102+62.38 | -         | -         | SF   | 49       |
| 12      | 6161025   | Channelizers                                                                                                           | 10+34.80      | 17+32.59 | 100+00.00     | 110+19.39 | 200+08.12 | 205+59.62 | EA   | 100      |
| 13      | 6181000   | Mobilization                                                                                                           | 10+34.80      | 17+32.59 | 100+00.00     | 110+19.39 | 200+08.12 | 205+59.62 | LS   | 1        |
| 14      | 6274000   | Contractor Furnished Surveying and Staking                                                                             | 10+34.80      | 17+32.59 | 100+00.00     | 110+19.39 | 200+08.12 | 205+59.62 | LS   | 1        |
| 15      | 7261015   | Storm Sewer (15" RCP)                                                                                                  | -             | -        | 102+59.69     | 102+62.60 | -         | -         | LF   | 36       |
| 16      | 7310000   | Storm Sewer Structure (Grated Inlet with Side Intake)                                                                  | -             | -        | 102+58.50     | 102+63.03 | -         | -         | EA   | 2        |
| 17      | 7320615A  | Precast Concrete Flared End Section, 15"                                                                               | -             | -        | 102+61.19     | 102+63.69 | -         | -         | EA   | 1        |
| 18      | 8061007A  | Inlet Check                                                                                                            | -             | -        | 102+56.22     | 102+65.06 | -         | -         | EA   | 2        |
| 19      | 8061019   | Silt Fence                                                                                                             | 10+79.91      | 17+14.45 | 100+13.93     | 110+01.83 | 200+11.82 | 205+37.59 | LF   | 2,366    |
|         |           | <b>SIGNING/STRIPING/SIGNALS ITEMS</b>                                                                                  |               |          |               |           |           |           |      |          |
| 20      | 6161006   | "Road Work Ahead" Sign (W20-1)                                                                                         | 10+34.80      | 17+32.59 | 100+00.00     | 110+19.39 | 200+08.12 | 205+59.62 | EA   | 4        |
| 21      | 6161006   | "End Road Work" Sign (G20-2)                                                                                           | 10+34.80      | 17+32.59 | 100+00.00     | 110+19.39 | 200+08.12 | 205+59.62 | EA   | 4        |
| 22      | 6161006   | "Shoulder Work Ahead" Sign (W21-5)                                                                                     | 10+34.80      | 17+32.59 | 100+00.00     | 110+19.39 | 200+08.12 | 205+59.62 | EA   | 4        |
| 23      | 6161006   | "One Lane Road" Sign (W20-4)                                                                                           | 10+34.80      | 17+32.59 | 100+00.00     | 110+19.39 | 200+08.12 | 205+59.62 | EA   | 4        |
| 24      | 6161006   | "Flagger" Sign (W20-7a)                                                                                                | 10+34.80      | 17+32.59 | 100+00.00     | 110+19.39 | 200+08.12 | 205+59.62 | EA   | 4        |
| 25      | 6161006   | "Road Narrows" Sign (W5-1)                                                                                             | 10+34.80      | 17+32.59 | 100+00.00     | 110+19.39 | 200+08.12 | 205+59.62 | EA   | 4        |
| 26      | 6161006   | "Sidewalk Closed" Sign (R9-9)                                                                                          | 10+34.80      | 17+32.59 | -             | -         | 202+37.51 | 203+22.16 | EA   | 2        |
| 27      | 6161006   | "Sidewalk Closed Use Other Side" Sign (R9-10)                                                                          | 10+34.80      | 17+32.59 | -             | -         | 202+37.51 | 203+22.16 | EA   | 2        |
| 28      | 6161031   | Type III Moveable Barricade with Type C Warning Lights                                                                 | 10+34.80      | 17+32.59 | 100+00.00     | 110+19.39 | 200+08.12 | 205+59.62 | EA   | 6        |
| 29      | 6161099   | Changeable Message Sign with Communication Interface, Contractor Furnished, Contractor Retained                        | 10+34.80      | 17+32.59 | 100+00.00     | 110+19.39 | 200+08.12 | 205+59.62 | EA   | 4        |
| 30      | 6200035   | Pavement Marking - Mid-Block Crossing White (Standard Waterborne)                                                      | -             | -        | -             | -         | 202+98.92 | 203+04.92 | SF   | 75       |
| 31      | 9031200   | Sign Relocation on New Post (per location, regardless of the number of signs)                                          | 11+30.37      | 17+09.63 | 100+75.48     | 110+01.96 | 200+23.13 | 205+35.09 | EA   | 12       |
| 32      | 9035000   | "Crosswalk" Sign (W11-2)                                                                                               | -             | -        | -             | -         | 202+98.92 | 203+10.93 | EA   | 2        |
| 33      | 9035000   | "Downward Arrow" Sign (W16-7p)                                                                                         | -             | -        | -             | -         | 202+98.92 | 203+10.93 | EA   | 2        |
|         |           | <b>BICYCLE/PEDESTRIAN FACILITY ITEMS</b>                                                                               |               |          |               |           |           |           |      |          |
| 34      | 6081012   | Detectable Warning Device                                                                                              | 17+13.53      | 17+19.85 | 100+14.03     | 110+00.85 | 200+16.59 | 205+45.72 | SF   | 95       |
| 35      | 6086000   | Concrete Sidewalk, 4"                                                                                                  | 10+37.75      | 17+19.85 | 100+14.03     | 110+01.35 | 200+16.59 | 205+46.22 | SF   | 7,477    |
| 36      | 6086100   | Concrete Step with Handrail (Remove and Replace)                                                                       | 15+29.43      | 16+97.26 | 101+36.29     | 101+43.87 | 201+26.71 | 201+29.04 | EA   | 6        |
|         |           | <b>LANDSCAPING/STREETSCAPING ITEMS</b>                                                                                 |               |          |               |           |           |           |      |          |
| 37      | 8031000   | Sodding                                                                                                                | 10+34.80      | 17+14.85 | 100+00.00     | 110+04.55 | 200+11.32 | 205+40.72 | SY   | 654      |

314-842-4033 (tel.)  
314-842-5957 (fax)  
www.cochraneeng.com

**COCHRAN**

Civil Engineering  
Land Surveying  
Architecture  
Site Development  
Master Planning  
General Consulting

ENGINEERING CERTIFICATE OF AUTHORITY NUMBER - 2007006937  
LAND SURVEYING CERTIFICATE OF AUTHORITY NUMBER - 2007004529

STATE OF MISSOURI

**TARY TODD**

NUMBER  
E-24182

5/17/26

TARY TODD  
NO. E-24182  
STATE OF MISSOURI  
REGISTERED PROFESSIONAL ENGINEER  
FOR SC ENGINEERING LLC,  
DBA COCHRAN

THIS SHEET HAS BEEN SIGNED,  
SEALED AND DATED ELECTRONICALLY

THE PROFESSIONAL'S SEAL AFFIXED TO  
THIS SHEET APPLIES ONLY TO ITEMS  
ON THIS SHEET. ALL DRAWINGS OR  
OTHER DOCUMENTS NOT EXHIBITING  
THIS SEAL SHALL NOT BE CONSIDERED  
PREPARED BY THE PROFESSIONAL.

WALTON ST. AND JEAN ST.  
SIDEWALKS TO SCHOOLS  
FEDERAL PROJECT NO. TAP-5489(615)  
CITY OF ST. CLAIR, MISSOURI

QUANTITY SHEET

REVISION:  
DATE:  
DATE:  
DATE:  
DATE:

DWN BY: M.R.B.  
DATE: MAY 2026  
SCALE: NO SCALE  
PROJ. NO: SC23-1512  
DWG. NO:

APPD BY: T.D.T.  
DATE:  
SCALE:  
PROJ. NO:  
DWG. NO:

Q-1